

**DATE: Thursday, June 4, 2026**

**ITB 26-046 IS AMENDED AS FOLLOWS:**

1. This ITB Schedule of Events updates and confirms scheduled ITB dates. **Any revision or new text is highlighted.**

**SCHEDULE OF EVENTS**

<p><b>NOTICE: The Institution reserves the right, at its sole discretion, to adjust this schedule, as it deems necessary. The Institution will communicate any adjustment to the Schedule of Events to the potential Bidders.</b></p>		
EVENT	TIME	DATE ( <u>all</u> dates are Institution business days)
1. APSU Issues ITB 26-046		<b>Friday, May 15, 2026</b>
2. Pre-Bid Meeting Location: Procurement Services' Conference Room505 York Street, Clarksville, TN 37040	<b>2:00 p.m.</b>	<b>Thursday, May 21, 2026</b>
3. Written Questions/Comments Deadline	<b>4:30 p.m.</b>	<b>Thursday, May 28, 2026</b>
4. Institution Responds to Written Questions/Comments. Questions and Answers	<b>4:30 p.m.</b>	<b>Thursday, June 4, 2026</b>
5. Bid Deadline  If hard copy, delivered to: 505 York Street Clarksville, TN 37040  with "ITB 26-046" on the outside of the package.  If electronic to: <a href="mailto:waltonp@apsu.edu">waltonp@apsu.edu</a>  with "ITB 26-046" in the subject line.  If you are a contractor bidding on a project and it is over \$25,000, please fill out the <a href="#">License Information Template</a> (PDF) and submit with your bid. This must be on the front of the sealed envelope or, if submitted electronically, the first page of your bid. For more information, please visit the <a href="#">Tennessee Department of Commerce and Insurance</a> .  <b><i>There will be no public bid opening.</i></b>	<b>4:30 p.m.</b>	<b>Thursday, June 11, 2026</b>
6. Bid Award		<b>Monday, June 15, 2026</b>

7. Certificate of Insurance (COI) Received by Procurement		<b>Thursday, June 25, 2026</b>
8. Performance Bond Due Received by Procurement		<b>Thursday, June 25, 2026</b>
<b>Work to begin after issuance of purchase order but to be completed by July 26, 2026.</b>		

**2. APSU responses to questions and comments in the table below to amend and clarify this ITB.**

Any restatement of ITB text below shall NOT be construed as a change in the actual wording of the ITB document.

ITB SECTION		QUESTION / COMMENT	APSU RESPONSE
	1.	Has anything been done to the site area already? Can we look at the area?	A test excavation has been completed. There is a fiber bank that runs along the edge of the excavation site. There is a perimeter drain as well but neither will hinder access nor work.
	2.	How deep is the area now?	Test excavation is roughly 2' – 2.5'.
	3.	What is the cap volume?	Up to 3 cubic yards. In line with schedule of quantities (page 3 GNAS250050 Fortera Stadium Dropout – IFB Plans.pdf)

ITB SECTION		QUESTION / COMMENT	APSU RESPONSE
	4.		<p>A concrete truck will not be allowed on the field. A pump must be used with a layer of ground protection underneath to not damage the turf.</p>
	5	<p>Where is the best access for the concrete truck and pump? Which has the least amount of traffic?</p>	<p>One option is along the fence and the other is by the lay down area. The summer classes are in session, but the volume is very light compared to Fall/Spring. The project must be completed by July 26<sup>th</sup>.</p>
	6.	<p>Is a hammer drill the expected method?</p>	<p>APSU is open to/will consider proprietary/vendor specific methods for excavation and remediation after the bid award.</p>
	7.	<p>Is seed and straw the expectation to repair areas used during the project?</p>	<p>Yes. Fescue is preferred and would only be applicable in the lay down area.</p>

ITB SECTION		QUESTION/COMMENT	APSU RESPONSE
	8.	Is there a schedule of cost breakdown?	The cost currently reflects the all-encompassing expense. APSU will add the cost breakout information.
	9.	Is the test drilling report in the packet?	It was not attached. It will be added by amendment and attached with the Question/Comments on June 4 <sup>th</sup> .
	10.	Should contractors price out treating directly beneath the track for this bid?	If it is determined during remediation that a treatment is needed beneath the track, a change order will be requested.
	11.	Is there a concrete wash out already on campus for drill rigs and concrete trucks?	No. Contractors are responsible for providing a washout system. This can be in the lay down area.

ITB SECTION		QUESTION/COMMENT	APSU RESPONSE
	12.	Is there access to water?	<p>Yes. There are two ¾” hose spigots beneath the west side seating, or there is a fire plug between the two access gates on Henry St. If the fire plug is used, the contractor must coordinate with Clarksville Gas and Water prior to this work beginning in order to obtain proper permits and metering.</p>
	13.		<p>Document Grouting Program added to the bid documents.</p>